



- GENERAL NOTES -**
1. All wyes and laterals to be located in the field. All Manholes to be Riv. City Std. No. 500. Maximum vertical spacing of steps in all manholes shall be 12".
 2. All laterals to be 6" and extended to the property line.
 3. All construction shall be in accordance with Standards and Specifications No. 460 of the City of Riverside, Department of Public Works. Pipe shall be double per Case II, Std. Dwg. # 452.
 4. It shall be the responsibility of the contractor to clear the right-of-way in accordance with the provisions of the law as it affects each utility including irrigation lines and appurtenances and at no extra cost to the City.
 5. BENCH MARK: Top 1 1/2" iron pipe at the center line intersection of Palm Ave and Tequesquite Ave. Elevation 783.31

FB. 726/40

J. F. DAVIDSON - CIVIL ENGINEER
R.E. NO. 862
RIVERSIDE, CALIFORNIA

APPROVED BY *J. F. Davidson* DATE 2-22-61

CITY OF RIVERSIDE, CALIFORNIA
DEPARTMENT OF PUBLIC WORKS

SEWER PLAN & PROFILE
PALM AVENUE
RIVERSIDE DEVELOPMENT CO.
R. S. No. 576

HORIZ. SCALE 1"=40' VERT. SCALE 1"=4'

MARK	DATE	DESCRIPTION
★	12-11-61	"As Built" H. Ball

APPROVED BY *J. F. Davidson* DATE 3/1/61

DRAWN BY *W. H. W.*

CHECKED BY *W. H. W.*

RECOMMENDED BY *A. K. K.* ASSISTANT CITY ENGINEER

S-277