


BENCH MARK
 Nail & Lead in East Curb of
 Streeter Ave. 135' South of
 Mt. View Elev. 786.82
 F.B. 29/59 & 4/16/48

NOTES
 Construction shall be in accordance
 with the City of Riverside Department
 of Public Works Specifications No. 460
 and standard drawings.
 Pipe shall be bedded per Case II Std. Dwg. 452
 House Connections to be located in field.

QUANTITY ESTIMATE
 8" V.C.P. ----- 620'
 4" V.C.P. ----- 594'
 8"x4" Wyes ----- 18
 Std 500 M.H. ----- 3
 Conc. per Std. 580 ----- 2.8 cu. yd.

Contractor shall expose flow line of existing
 36" water line on Streeter Ave. and notify the
 Engineer before laying sewer pipe so the
 Engineer can check the clearance between
 the sewer & water lines.



ALBERT A. WEBB ASSOCIATES
 CIVIL ENGINEERS - RIVERSIDE, CALIFORNIA
 APPROVED *Albert A. Webb* DATE 8/23/61
 No. 9876

CITY OF RIVERSIDE, CALIFORNIA
 DEPARTMENT OF PUBLIC WORKS

REVISION		DESCRIPTION
MARK	DATE	DESCRIPTION
*	12-1-61	"As Built" H. Ball

SEWER PLAN & PROFILE
STREETER AVENUE
LANTANA STREET
TRACT 2258

DATE Sept. 61 SCALE Horiz. 1"=50'
 Vert. 1"=5'
 DRAWN RRS W.O. 61-154
 CHECKED D.R.S. F.B. 4/16/51
 OP ADD

APPROVED BY *[Signature]*
 DIRECTOR OF PUBLIC WORKS
 DATE Sept. 5, 1961 SHEET 1 OF 1

PROFILE

SUBMITTED	BY	DATE
NOTED		
GRADES CHECKED		
BY M.S. NIELSEN		
BY C. W. CHAMBERS, CHGO		

PLAN

SUBMITTED	BY	DATE
NOTED		
ALIGNMENT CHECKED		
BY G. W. WYSE		
BY G. W. WYSE		