



Bench Mark:
2½" Spike in pole
15107-J at N.E. Cor.
of Industrial Ave: &
Fremont St.
Elev. 777.10
~~City Elevation = 776.97 F.B. 930/124~~

QUANTITY ESTIMATE

Cb & Gutter	259	lin ft.
Cb only	38	lin. ft.
Cross Gutter	277	sq. ft.
Pavement & Base	3,868	sq. ft.
2"x4" Header	45	lin ft.
Excavation	100	cu. yds.
Over haul	2	Tons







TYPICAL SECTION
FREMONT ST.
T.I. = 6

GENERAL NOTES:

1. It shall be the responsibility of the contractor to clear the right of way in accordance with the provisions of law as it affects each utility including irrigation lines and appurtenances and at no cost to the city.
2. Construction shall be in accordance with the city of Riverside Department of Public Works, Specifications No. 461 and Standard Drawings.
3. Prime coat, seal coat, and paint binder are required.
4. The Contractor shall submit to the City Engineer two weeks prior to starting work a Proposal for the City Portion of the work. The Contractor shall also submit to the City a copy of the Bid to the Developer.
5. Trim edge of existing pavement, where new paving joins existing pavement, to a clean, straight line. Construct a match-up paving as shown and overlay as directed in the field to produce a smooth crown section. Engineer Estimates overlay to be 2 Tons.
6. Driveways shall be Constructed per Std Drawing No 302.



TYPICAL SECTION INDUSTRIAL AVE.
T.I. = 6

JOHN H. HACKER CIVIL ENGINEER
39780 KIT AVE., HEMET CALIF.
John H. Hacker Oct. 29, 70
R.C.E. 14614

MARK	REVISIONS	APPR.	DATE

DESIGNED BY ____ DRAWN BY ____ CHECKED BY TM

CITY OF RIVERSIDE, CALIFORNIA
DEPARTMENT OF PUBLIC WORKS

APPROVED BY	BY	DATE
OFFICE ENGINEER		12/15/70
PARK DEPARTMENT	—	—
TRAFFIC DIVISION		12/15/70
ASSISTANT CITY ENG.		12/15/70

APPROVED BY William D. Kerkhum
DIRECTOR OF PUBLIC WORKS
DATE 12/30/70

STREET PLAN & PROFILE
FREMONT ST. West Side 162.5' of Industrial
INDUSTRIAL AVE. South Side 165' W. of Fremont
HORIZ. SCALE: 1" = 40' VERT. SCALE: 1" = 4'

PROJECT NO. R-1464
SHEET 1 OF 1
FILE NO.