N'LY EDGE OF PAVEMENT PROFILE

EXISTING GROUND 33' NORTH OF ℄

EDGE OF PAVEMENT FROM STATION 11+26 TO 16+07.05 TO BE PER TYP. SECTION — 0.34' BELOW ℄ PROFILE.

JOIN EX. PVMT & FEATHER TO THE SATISFACTION OF THE CITY ENGINEER.

EXISTING E.P. 7' W OF ℄

CENTERLINE PROFILE

EX. GROUND @ ℄

FEATHER TO THE SATISFACTION OF THE CITY ENGINEER. CONST. A.C. OVERLAY FROM STA. 10+00 to STA. 10+07.

10" C.M.P.

GRADED SWALE PROFILE

CONSTRUCT GRADED SWALE PER TYPICAL SECTION

EDGE OF PAVEMENT FROM STA. 10+22 (E.C.) TO BE PER TYP. SECTION — 0.06' BELOW ℄ PROFILE.

EXIST. CONC. ARCH CULVERT, MASONRY OR R.C.P. FLOWLINE PROFILE

CLEAN OUT EXISTING CONCRETE ARCH CULVERT & /OR 10" R.C.P. DRAIN PIPES. REMOVE & REPLACE BROKEN PORTIONS OF CULVERTS, AS REQUIRED TO RETAIN ACCESS POINTS AT EXISTING WIDTHS.

PROFILE SCALES
HORIZ. 1" = 40'
VERT. 1" = 4'

S'LY EDGE OF PAVEMENT PROFILE

PAVEMENT TRANSITION DETAIL

SCALE: 1"=10'

X-SEC. FOR N'LY HALF OF STREET TO BE PER TYPICAL SECTION FROM STA. 11+26 to 16+07.05.

X-SEC. FOR S'LY HALF OF STREET TO BE PER TYPICAL SECTION FROM STA. 10+22 to 16+07.05.

BENCH MARK

P.K. NAIL IN S'LY HEADWALL OF DRAIN FLUME ON W'LY SIDE JEFFERSON ST. S'LY OF GAGE CANAL, STAMPED FC-D ELEVATION 1007.0000

GENERAL NOTES

1. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO CLEAR THE RIGHT OF WAY IN ACCORDANCE WITH THE PROVISIONS OF LAW AS IT AFFECTS EACH UTILITY INCLUDING IRRIGATION LINES & APPURTENANCES & AT NO COST TO THE CITY.
2. CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE CITY OF RIVERSIDE, DEPARTMENT OF PUBLIC WORKS, STANDARD DRAWINGS, & THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION, 1970 EDITION.
3. TRIM EDGE OF EXISTING PAVEMENT WHERE NEW PAVEMENT JOINS TO A SMOOTH, STRAIGHT LINE. CONSTRUCT MATCH-UP PAVING AS SHOWN ON PLAN & OVERLAY PAVING AS DIRECTED IN THE FIELD TO PRODUCE A SMOOTH SECTION.
4. ALL FLAGGED ELEVATIONS SHALL BE STAKED IN THE FIELD BY THE PRIVATE ENGINEER.
5. THE PRIVATE ENGINEER SIGNING THESE PLANS IS RESPONSIBLE FOR ASSURING THE ACCURACY & ACCEPTABILITY OF THE WORK HEREON. IN THE EVENT OF DISCREPANCIES ARISING DURING CONSTRUCTION AS A RESULT OF ERRORS OR OMISSIONS, THE PRIVATE ENGINEER SHALL BE RESPONSIBLE FOR DETERMINING AN ACCEPTABLE SOLUTION & REVISING THE PLANS FOR APPROVAL BY THE CITY.
6. PROTECT 10" STEEL IRRIGATION PIPE TO SATISFACTION OF GAGE CANAL CO. CALL 48 HOURS PRIOR TO COMMENCING WORK. TELEPHONE (714) 780-1330 OR 780-2310. WORK TO BE PERFORMED @ NO COST OR LIABILITY TO GAGE CANAL CO.
7. DEVELOPER TO GIVE CITY WATER DIVISION FIVE (5) WORKING DAYS WRITTEN NOTICE PRIOR TO START OF CONSTRUCTION AND TO ALLOW CITY TEN (10) WORKING DAYS FOR COMPLETION OF WORK. (714) 787-7611.
8. EDGE OF CUT BANKS TO BE 2' MINIMUM FROM TRUNK OF PALM TREES. EXISTING PALM TREES TO BE PROTECTED IN PLACE.

TYPICAL SECTION — SUMMIT STREET

HORIZONTAL SCALE 1"=10'; VERTICAL SCALE-1"=2'

CONSTRUCT 3½" A.C. OVER COMPACTED NATIVE (T.I. = 5) PER S.D. #202, R=57.

CONSTRUCT SWALE-GRADE PER PROFILE — STA. 10+24 TO STA. 12+66 RT. FROM STA. 12+66 TO 16+07.04 EXIST. CONC. CULVERTS & DRAIN PIPES TO BE CLEANED AND SWALE CONSTRUCTED TO THE GRADES SHOWN ON THE PROFILE.

SUMMIT STREET

NOTE:

ALL ACCESS POINTS TO THE PROPERTY TO THE SOUTH TO BE RETAINED @ EXISTING WIDTHS.
ANY BROKEN PIPE NOT WITHIN EX. ACCESS POINTS MAYBE REMOVED & SWALE CONSTRUCTED PER TYPICAL SECTION.

CURVE DATA

(A) Δ = 89°59'50" R = 15.00' L = 23.56' T = 15.00'
(B) Δ = 90°00'10" R = 15.00' L = 23.56' T = 15.00'

* AS BUILT 9/16/81

PACIFIC TELEPHONE — APPROVED BY: DK Sumner 6/17/81 DATE	CITY WATER DEPT. — APPROVED BY: Fred Kautz 7/6/81 DATE	STAN SCHUPP & ASSOC. PLANNING, ENGINEERING, SURVEYING RIVERSIDE, CA. (714) 781-0811 PREPARED UNDER THE SUPERVISION OF: Stan Schupp R.C.E. 16,568 6/8/81 DATE	CITY OF RIVERSIDE, CALIFORNIA PUBLIC WORKS DEPARTMENT
GAGE CANAL CO. — John M. Hocking 7-7-1981 DATE	DATE		APPROVED BY: DIRECTOR OF PUBLIC WORKS — DATE 9/16/81

MARK	REVISIONS	APPR.	DATE

DESIGNED BY JGS DRAWN BY JJC CHECKED BY JGS

PLAN & PROFILE OF STREET IMPROVEMENTS FOR SUMMIT STREET N'LY & E'LY CORNER P.M. No. 10425

SCALE: HORIZ.-1"=40', VERT. 1"=4'

ACCOUNT No.

DRAWING NUMBER R-2380

SHEET 1 OF 1

PD-108